

CEDAR SHAKE

Description	Qty	Line total
Roofing		
Tear Off - Standard		\$0.00
Labor charge for tear off of one layer of standard asphalt shingles		
Brava Multi Width Synthetic Cedar Shark	10	
Brava Hip & Ridge Steep Low Hip & Ridge		
Brava Hip & Ridge Steep Slope Hip & Ridge	15	
High Temp Ice & Water Shield	3	
Synthetic Underlayment	2	
Brava Cedar Starter Tile	100	
Greater than 12/12 Additional Labor for Steep Roof Additional Saftey/OSHA requirements	10	
Description	Qty	Line total
Flashing		
Metal Valley	31	
Galvanized Steel W-Valley Installed with anti corrossive nails Ice and Water Shield installed below and covering both ends of the W-Valley 26 guage		
Color:		
Custom Bent Gutter Apron 25 Guage	73	
Color:		
Step Flashing 9x14	13	
Color: Bronze		
F Style Drip Edge for designer synthetic slate shingle installation	18	
Color:		
Coping Metal	85	
Color:		
Description	Qty	Line total
Gutters & Downspouts		
Detach and Reset Gutter Runs	82	
Detach and Reset Downspout	24	
Description	Qty	Line total
Misc		
Permit	1	
City of Oakbrook Building Permit		
Nails Stinger NailPac EG Ring Shank Coil Roofing Nails	1	
1-1/4" X .120" 7.2M/BX		

[illegible]